

AVT

ACOUSTICAL VINYL TILE








WOOD

Technical Specifications

Sizes

| Size | Thickness | Pcs/Carton | Sqft/Carton | Lbs/Carton |
|--------------|-----------|------------|-------------|------------|
| 6 in x 48 in | 5.0 mm | 10 pcs | 20 sqft | 33.5 lbs |
| 7 in x 48 in | 5.0 mm | 10 pcs | 23.36 sqft | 39.13 lbs |

Testing

| Test Item | | Standard | Results |
|---------------------------|---|-------------------------|--------------------------------|
| Level of use |  | ISO 10874 | 33, Heavy commercial |
| Static load limit | | ASTM F970 | 2,000 psi |
| Squareness & Straightness |  | ISO 24342 ASTM F2055 | Passes No deviation, ≤0.1mm |
| Flexibility | | ASTM F137 | Passes |
| Dimensional stability |  | ASTM F2199 | Passes |
| Resistance to chemicals | | ASTM F925 | Passes, No defects |
| Resistance to light |  | ASTM F1515 | Passes |
| Resistance to heat | | ASTM F1514 | Passes |
| Fire resistance |  | ASTM E648 | Passes |
| Smoke density | | ASTM E662 | Passes |
| Slip resistance |  | ASTM E303 | Passes |
| Indoor air quality | | | Low VOC, Floor Score certified |
| Sound insulation |  | ISO 10140 | >15db Rating 70, STC Rating 63 |


Caution

Condition in at least 19°C (67°F) or the normal temperature of the room where the product is to be laid, for at least 48 hours before installing. Cartons must be stacked less than 5 high and tiles removed 30 minutes before use. The site conditions must be maintained during installation and for at least 48 hours after completion. Evo Floors, LLC will not accept claims where these instructions have not been followed.

Manufacturing

ISO 9001 Quality Management System
 ISO 14001 Environmental Management System
 OSHAS 18001 Occupational Health and Safety Management System

Certification



Please visit www.evofloors.com for detailed installation / maintenance guides and technical information.