

Technical Specifications

Sizes

Size	Thickness	Pcs/Carton	Sqft/Carton	Lbs/Carton
18 in x 18 in	5.0 mm	10 pcs	23 sqft	37 lbs

Testing

Test Item	Standard	Results
Level of use	ISO 10874	34, Heavy commercial
Static load limit	ASTM F970	2,000 psi
Squareness & Straightness	ISO 24342 ASTM F2055	Passes No deviation, ≤0.1mm
Flexibility	ASTM F137	Passes
Dimensional stability	ASTM F2199	Passes
Resistance to chemicals	ASTM F925	Passes, No defects
Resistance to light	ASTM F1515	Passes
Resistance to heat	ASTM F1514	Passes
Fire resistance	ASTM E648	Passes
Smoke density	ASTM E662	Passes
Slip resistance	ASTM E303	R11, Anti-slip tiles, secure for both wet and dry environments
Indoor air quality		Low VOC, Floor Score certified
Sound insulation	ISO 10140	>15db Rating 70, STC Rating 63
	.00 101.10	- Todo Rating 7 0, 51 0 Rati

Caution

Condition in at least 19° C (67° F) or the normal temperature of the room where the product is to be laid, for at least 48 hours before installing. Cartons must be stacked less than 5 high and tiles removed 30 minutes before use. The site conditions must be maintained during installation and for at least 48 hours after completion. Evo Floors, LLC will not accept claims where these instructions have not been followed.

Manufacturing

ISO 9001 Quality Management System
ISO 14001 Environmental Management System
OSHAS 18001 Occupational Health and Safety Management System

Certification











